

# **SVS UNITECH ELEVATORS**

## **Elevating You To New Heights**

### **QUOTATION**

To Date: 22/01/2024 **Product of Supply: 1 TON LOAD COMMERCIAL LIFT G+2**Quo Ref

**Elevator Specification** 

Elevator Specification		
Туре		
Brand		
Number of Lifts		1
Basic Specification:		
1	Capacity (Kg)	1 TON kg 16 persons
2	Speed(m/s)	1m/s
3	Speed Control System	VVVF
4	Control System	Simplex
5	Traction Electric Indirect	Traction
6	Slops	3 stops
7	Door Openings	Normal door
8	Serving Floors	G+2
9	Power Voltage	380V AC
10	Lighting Voltage	220 AC
11	Frequency	50 HZ
12	Machine Room	MACHINE ROOM MODAL
13	Counterweight	Filler weight
14	Machine Type	Faer/no
15	Steel Wire Rope	Imported
II Shaft:	1	1
1	Shaft Construction	Customer
2	Clear Dimensions	1800*1800
3	Travel	12500mm
4	Pit Depth	1500mm
5	Overhead	4500mm
III Car: Local		
1	Car Walls	SS steel
2	Car Dimentions (mm*mm)	Internal 700*800
3	Car Clear Height(mm)	2133mm
4	Flooring	MS (painted)
5	Handrail	SS
6	Entrance Column	Normal door
7	Ceiling	SS with custom
8	Buffers	Spring
9	Digital Indicator	LCD
IV Car Operator Panel:		
1	COP	UP/DN ARROWS, WITH ALL FLOORS
V Car Door:		
1	Door Type	AUTO DOOR
2	Door Size (mm*mm)	700MM
3	Door Safety	WITH DOOR
4	Door Mechanism	AUTO DOORS
5	Door Controller	Power to safety
6	Door Finishing	SS FINISH

No.15, Sarayu park, New Colony, 2nd Main Road, Chennai-600 044.

GSTIN: 33ABOCS4534K1ZZ



# **SVS UNITECH ELEVATORS**

### **Elevating You To New Heights**

VI Landing Door:		
1	Door Type	AUTO DOOR SS
2	Door Size (mm*mm)	700 MM
3	Panel at Main Floor	SS FINISH
4	Panels at Other Floors Hair Line	YES
5	Jamb at Main Floor Hair Line	YES
6	Door Mechanism	NO
7	Door Finishing	SS FINISH
VI Landing Push Plate:		
1	Cabin Position Indicator	SAME LANING LOP
2	Direction Arrow	UP/DN
3	Push Botton Finish	SS FINISH
VII Main Controller:		
1		
2		
3	Control	MOBARA CONTROL
4		
5		
6		440 V TOTAL AC

#### **Safety Features:**

- 1. Overload relay of main traction motor safety
- 2. Main circuit breaker device.
- 3. Phase failure device
- Electrical safety switch
- 5. Electro Mechanical door lock
- 6. Car Maintenance push button
- 7. Electrical fuses

#### TERMS AND CONDITIONS

#### PAYMENT SCHEDULE

50% Advance along with the order.

40% At the time of delivery of material at site

10% After Handling over the lift

#### **Completion Period:**

With in 02 months from the confirmation of order/ advance payment/ handling over the clear site

### Warranty:

One year free parts except consumable and negligence/misuse on parts by user.

#### **EXCEPTION:**

All type of civil work on account of buyer which include scaffolding, cutting, fitting, site store, lighting.

Validity: 15 days

Note: The Above price is exclusive of all taxes.

No.15, Sarayu park, New Colony, 2nd Main Road, Chennai-600 044.

GSTIN: 33ABOCS4534K1ZZ